
# Appendix D2

# Application of the Metropolitan Planning Organization Travel Demand Model





1

10

15

16

17

18 19

20

21

22

23

24

25

26

27

28



# 1.1 INTRODUCTION


- 2 The Alamo Area Metropolitan Planning Organization (formerly the San Antonio Bexar
- 3 County Metropolitan Planning Organization) (MPO) 2035 travel demand model was
- 4 used to forecast future traffic volumes for various scenarios analyzed for the US 281
- 5 Environmental Impact Statement (EIS) project. Note, the MPO adopted *Mobility 2040* on
- 6 December 8, 2014; however the travel demand model associated with this plan was not
- 7 available at the time of this analysis. The 2035 travel demand model was the most
- 8 current data available at the time. This memorandum documents the application of the
- 9 2035 travel model for the project.

# 1.2 MPO TRAVEL DEMAND MODEL

- 11 The MPO calibrated and validated the travel demand model to year 2008 conditions.
- 12 The MPO provided the most current version of the 2035 travel model network and trip
- 13 table for each successive stage of screening. Illustrations of the model are provided in
- 14 the following figures:
  - **Figure 1** displays the traffic analysis zone system.
  - **Figure 2** displays the Year 2008 regional network.
  - **Figure 3** displays the 2035 regional network provided by the MPO containing the region's planned improvements to the roadway system, including improvements to the US 281 Corridor.
  - **Figure 4** displays the 2035 network in the vicinity of the US 281 project corridor area.
  - A primary input of the model is future estimates of population and employment, distributed geographically by Traffic Analysis Zone. The future socioeconomic data set used for the US 281 screening process was the MPO adopted 2035 socioeconomic data scenario (TOD + Infill) for the region. The "Current Trends" 2035 scenario was used for some sensitivity analyses to gain an understanding of the capacity needed under that socioeconomic scenario.
- 29 The travel model is capable of providing travel demand volume projections at a daily
- 30 level. Peak hour results are limited to link speed and volume-to-capacity (v/c) ratios.
- 31 The MPO model uses input parameters including speed and travel time based on
- 32 observed congested or peak hour conditions. The model assigns trips to roadways
- 33 under these peak conditions, and reports forecasted peak hour speeds and v/c ratios,
- 34 and daily traffic volumes.




# 1 Figure 1: Traffic Analysis Zone System



Source: MPO Travel Demand Model, 2009

# 4 Figure 2: Year 2008 Model Network






Source: MPO Travel Demand Model, 2009

<u>2</u>


# 1 Figure 3: Year 2035 Model Network



Source: MPO Travel Demand Model, 2009

Source: MPO Travel Demand Model, 2009

# Figure 4: Year 2035 Model Network – Study Area



56

2 3



Appendix D<sub>2</sub> May 2015

- 1 As with any simulation model, there are limitations to its capabilities. The US 281 project
- 2 corridor is located towards the edge of the boundary of the regional model and the
- 3 traffic analysis zones are relatively large. Large traffic zones inhibit the precision of the
- 4 localized volume forecasts. The coded network of the MPO model includes frontage
- 5 roads along freeways in locations as appropriate, but the model's assignment of traffic
- 6 activity to these frontage roads needs to be checked for reasonableness. The model does
- 7 not have a capability for estimating use of a high-occupant vehicle (HOV) facility. The
- 8 model has a minimal procedure for estimating toll road volume, which is traffic
- 9 assignment based. The toll procedure adds a cost in terms of travel time by converting
- 10 an assumed toll rate per mile with value-of-time assumptions, for links coded as toll
- 11 links.


12

13

### Model Application 1.2.1

# **Model Operation**

- 14 The model is implemented in the TransCAD software platform. TransCAD version 4.8,
- 15 Build 500 or higher, was used for all modeling exercises. Alternatives were tested using
- the Multi-Modal Assignment procedures in interactive mode, according to instructions 16
- 17 from the MPO. The parameters shown in **Figure 5** were used to run the model.
- 18 Figure 5: TransCAD Interactive Mode Parameters



19 20

D2-4

Source: MPO Travel Demand Model, 2009



# **Coding Assumptions**


Roadway improvements for capacity and facility type were coded per guidance from the MPO. For toll links, the toll code was flagged with a value of time of \$0.20 per minute (\$12.00 per hour) and a toll rate of \$0.15 per mile for autos and \$0.40 per mile for trucks.

Because the model does not have HOV or Managed Lane (a lane that is restricted to tolled vehicles and high occupant vehicles) capabilities, managed lanes were coded as tolled expressways with the cost of the toll reduced by 50 percent. In addition for managed lanes, the vehicle trip table was reduced to account for the increased amount of carpooling due to the inclusion of HOVs on the managed lane facility. To determine the trip table reduction, a select link analysis was employed to determine the set of typical origin and destination zones that use the US 281 project corridor. This subset of the regional trip table was reduced by about 2,500 trips. This corresponded to about a 3% reduction of directional vehicle trips that use the US 281 project corridor. The basis for this amount was the reported mode share experience in Houston and Dallas.

# 1.2.2 Interpretation of Model Results

A review of the 2008 model volumes compared to observed traffic counts on the US 281 project corridor was performed. It was found that the daily link model volumes typically compared favorably with the observed daily counts, with some link-to-link variability. **Figure 6** displays the comparison of counts to model volumes along the US 281 project corridor.





Source: Pape-Dawson, US 281 Super Street Study, 2009, US 281 EIS Team, 2010



11

# 1.3 LEVEL 2 AND 3 ALTERNATIVES MODELING

- 2 This section describes the modeling performed for Levels 2 and 3 alternatives screening.
- 3 The travel model was not employed for Level 1 screening.

# 4 1.3.1 Source Travel Model

- 5 For Level 2 screening, the latest version of the travel demand model was provided by
- 6 the MPO on October 21, 2009. For Level 3 screening, the MPO provided an updated
- 7 model in the form of model sets for the years 2008 and 2035 on December 29, 2009. The
- 8 transmitted 2035 model files were limited to origin-destination matrices and a
- 9 geographic network file. These trip tables created by the MPO reflected the adopted
- 10 2035 socio-economic data scenario (TOD + Infill) for the region.

# 1.3.2 2035 No-Build Network Model

- 12 A No-Build network model is used as a baseline to compare several build alternatives.
- 13 The network used for the model is defined to be the existing roadway system, together
- 14 with committed improvement projects as planned by the MPO outside of the specific
- action being proposed. The 2035 network provided by the MPO was used as the base
- 16 for the No-Build network. This network includes widening and upgrading the US 281
- 17 project corridor to a tolled expressway. This improvement was removed from the No-
- 18 Build network, and the US 281 project corridor was re-coded to 2008 conditions. The
- 19 detailed coding of the Super Street improvements was not included.

# 20 1.3.3 Level 2 2035 Build Networks

- 21 The 2035 Build networks were coded for several US 281 alternatives using the 2035 No-
- 22 Build network as a base. Numerous alternative scenarios were simulated with the travel
- 23 model to support the technical analysis for the US 281 Corridor Project. In Level 2, an
- 24 initial set of model runs of alternatives were completed. Table 1 provides a list and
- 25 description of the modeling scenarios performed for Level 2 alternative screening.



May 2015

# 1 Table 1: Level 2 Alternative Model Runs

Run Name	Base Network	O-D Table	Improvements	Quality Check	
2008 Base Test	2015 E+C	2008	None	Check	
2035 2015 E+C	2015 E+C	2035 on 2015	None	Check	
US-281_2035 F-1	2015 E+C	2035 on 2015	6-Lane Freeway between Loop 1604 and Borgfeld	Check	
US-281_2035 F-2	2035 F-1	2035 on 2015	8-Lane Freeway between Loop 1604 and Evans; 6-Lane Freeway between Evans and Borgfeld	Check	
US-281_2035 F-3	2035 F-2	2035 on 2015	8-Lane Freeway between Loop 1604 and Evans; 6-Lane Freeway between Evans and Borgfeld; 8-Lane Expressway between Borgfeld and Bulverde North	Check	
US-281_2035 E-1	2015 E+C	2035 on 2015	8-Lane Expressway between Loop 1604 and Borgfeld	Check	
US-281_2035 E-2	2015 E+C	2035 on 2015	10-Lane Expressway between Loop 1604 and Borgfeld	Check	
2035 2015 E+C - Trends	2015 E+C	2035 on 2015 CT	None; Current Trends Land Use Adjustment	Check	
US-281_2035 F-3 - Trends	2035 F-2	2035 on 2015 CT	8-Lane Freeway between Loop 1604 and Evans; 6-Lane Freeway between Evans and Borgfeld; 8-Lane Expressway between Borgfeld and Bulverde North; Current Trends Land Use Adjustment	Check	
US-281_2035 CT Expressway Alternative	2035 SAM	2035 CT	Expressway Alternative as transmitted by Austin (12/02/2009); Current Trends Land Use Adjustment	Check	
US-281_2035 T+I Expressway Alternative	2035 SAM	2035 T+I	Expressway Alternative as transmitted by Austin (12/02/2009); Adopted TOD + Infill (T+I) Land Use	Check	
US-281_2035 T+I Expressway Plus Alternative	2035 T+I Expressway	2035 T+I	Sensitivity Test – Added 1 additional lane per direction	Check	
US-281_2035 T+I Expressway Alternative (iteration2)	2035 T+I Expressway	2035 T+I	Expressway Alternative coded to match the recommended laneage.	Check	

<sup>2</sup> Source: US 281 EIS Team, 2010



# 1.3.4 Level 2 Results

5

6 7

8 9

10

11

12


13

14

2 Level 2 modeling aided in the development of Level 3 alternatives by providing general

- 3 guidance on the needed number of lanes through the US 281 project corridor. A
- 4 summary of daily volumes for the Level 2 alternatives is presented in **Figure 7**.

# Figure 7: Level 2 Daily Traffic Projections



Source: MPO Travel Demand Model, 2009, US 281 EIS Team, 2010

# 1.3.5 Level 3 2035 Build Networks

Level 2 alternatives were refined and altered to form the set of alternatives for analysis in Level 3 screening. **Figure 8** displays a summary of the Level 3 alternative roadway cross-section configurations for the US 281 project corridor. Some alternatives required several iterations of coding refinements to produce reasonable results. The description of Level 3 model run iterations is provided in **Table 2**.



# 1 Figure 8: Level 3 US 281 Corridor Configurations

# LEVEL 3 ALTERNATIVE CONFIGURATIONS

# PRELIMINARY DRAFT 2-24-2010

- ]	V	O BUILD	EU TET
ATIVE	А	OVERPASS	
ALTERNATIVE	В	OVERPASS (W/ UPGRADE TO PARALLEL FACILITIES)	#LANCO (IGO4 - BORGFELD) USTED AS 2 OR 4 LANES IN MTP
Æ	Δ	EXPRESSWAY	
ALTERNATIVE 2	В	EXPRESSWAY (TOLL)	
AL	c	EXPRESSWAY (MANAGED)	
ĮJ.	А	EXPRESSWAY (W/ HOV)	F.F.F. F.F. Hundard Toler
AL TERNATIVE	В	EXPRESSWAY (PARTIAL TOLL)	
ALT	С	EXPRESSWAY (W/ MANAGED LANES)	F.F.F
	Δ	ELEVATED EXPRESSWAY	BRIDGE BRIDGE C
ALTERNATIVE	В	ELEVATED EXPRESSWAY (TOLL)	THE BRIDGE OF BRIDGE
AL	c	ELEVATED EXPRESSWAY (W/ MANAGED LANES)	BRIDGE BRIDGE BRIDGE
		EXISTING LANES MANAGED LANE	THE GENERAL PURPOSE LANE TRENTAGE ROAD  THE HOV LANES THE PARALLEL ARTERIALS






# 1 Table 2: Level 3 Alternative Model Runs

Run Name	Short	ort Coded starting O-D Table		Improvements	Date
	Name	with			
US-281_Alternative 0 T+I No Build	0	2035 SAM	2035 T+I	No Build. Coded with simple node intersections	2/1/2010
US-281_Alternative 1B T+I Overpass + UPA	1B	Alternative 0	2035 T+I	Added interchanges at each intersection. Upgraded sections of the roadway to Freeway. Set capacity to 1500 vph. Bulverde and Blanco widened to 6 lanes.	2/4/2010
US-281_Alternative 1A T+I Overpass (4 Lane)	1A	Alternative 1 (prior)	2035 T+I	Bulverde and Blanco coded to match Alternative 0.	2/18/2010
US-281_Alternative 1D T+I Overpass (8 Lane)	1D	Alternative 1B (prior)	2035 T+I	Increase US-281 to 8 Lanes	2/18/2010
US-281_Alternative 1E T+I Overpass (10 Lane)	1E	Alternative 1B (prior)	2035 T+I	Increase US-281 to 10 Lanes	2/18/2010
US-281_Alternative 1C T+I Overpass (4 & 6 Lane)	1C	Alternative 1A (new)	2035 T+I	US-281 6 lanes to Stone Oak, 4 lanes to Borgfeld, no upgrades to parallel arterials	
US-281_Alternative 2A T+I Expressway (FREE)	2A	Alternative 0	2035 T+I	Coded to match Expressway Alternative from Austin. Coded mainline as General Purpose.	2/1/2010
US-281_Alternative 2B T+I Expressway (TOLL)	2B	Alternative 2A	2035 T+I	Coded mainline as toll.	
US-281_Alternative 2C T+I Expressway (HOT)	2C	Alternative 2A	2035 T+I	Coded to match HOT lane coding of 4C	2/18/2010
US-281_Alternative 2C-1 T+I Expressway (HOT)	2C-1	Alternative 2C	2035 T+I Factored for HOV	Ran with Matrix reduced by 78% to account for HOV	
US-281_Alternative 3A T+I Expressway + MGD (FREE)	3A	Alternative 2A	2035 T+I	Added express lanes, coded as General Purpose.	2/1/2010
US-281_Alternative 3A-1 T+I Expressway + MGD (FREE)	3A-1	Alternative 3A	2035 T+I Factored for HOV	Ran with Matrix reduced by 78% to account for HOV	2/17/10
US-281_Alternative 3B T+I Expressway + MGD (TOLL)	3B	Alternative 2A	2035 T+I	Added express lanes, coded as toll.	1/28/2010
US-281_Alternative 3C T+I Expressway + MGD (HOT)	3C	Alternative 2A	2035 T+I	Added express lanes, coded as HOT (overridden capacity of 1500 vph).	2/3/2010
US-281_Alternative 3C-1 T+I Expressway + MGD (HOT)	3C-1	Alternative 3C	2035 T+I Factored for HOV	Ran with factored Matrix to account for HOV	
US-281_Alternative 4A T+I Managed (FREE)	4A	Alternative 0	2035 T+I	Coded to match Alternative 3A from Austin. Coded expressway as General Purpose.	2/3/2010
US-281_Alternative 4B T+I Managed (TOLL)	4B	Alternative 0	2035 T+I	Coded to match Alternative 3A from Austin. Coded expressway as toll.	2/1/2010
US-281_Alternative 4C T+I Managed (HOT)	4C	Alternative 0	2035 T+I	Coded to match Alternative 3A from Austin. Coded expressway as HOT (overridden capacity of 1500 vph).	2/3/2010







Source: US 281 EIS Team, 2010

2


# 1.3.6 Level 3 Results

- 3 Level 3 modeling aided in the development of DRAFT EIS alternatives by providing
- 4 more specific results. A summary of daily volumes north of Redland for the Corridor
- 5 as well as parallel arterials for the Level 3 alternatives is presented in **Table 3**. In
- 6 preparation of the alternatives screening, travel model results were adjusted as
- 7 necessary for reasonableness. **Table 3** contains the measures of effectiveness for Level 3.

US 281 Final EIS



# 1 Figure 9: Level 3 Daily Traffic Projections



Source: MPO Travel Demand Model, 2009, US 281 EIS Team, 2010

4



May 2015

# 1 Table 3: Detailed Level 3 Measures of Effectiveness

		Alternatives									
Level 3 Criteria	Existing	2035									
				Overpass/	Expressway			Elevated Expressway			
		No Build	Overpass/ & Widen	Blanco Rd. & Bulverde	Non Toll	Toll	Managed	Non Toll	Toll ,	Managed	
Average Peak Hour Spe	eed (mph) -	Corridor									
U.S. 281 Corridor - All Lane Types	25	5	20	20		40			30	30	
U.S. 281 Corridor - Main lanes only	25	5	20	20	45		45				
Average Daily Traffic (	000s)										
South of Bulverde - U.S. 281 Corridor	40	75	120	105	130	120	120	125	115	115	
South of Bulverde - Blanco + Bulverde	20	45	30	40	20	25	25	20	25	25	
North of Sonterra - U.S. 281 Corridor	90	115	170	165	210	185	180	170	160	160	
North of Sonterra - Blanco + Bulverde	40	110	90	100	70	85	85	90	95	95	
LOS along U.S. 281 Cor	ridor - Perc	ent of Ce	nterline miles	5							
LOS A, B, C, or D	10%	5%	20%	35%		70%			60%		
LOS E	0%	0%	20%	5%		15%		10%			
LOS F	90%	95%	60%	60%		15%			30%		
LOS along Parallel Faci	lities (Bulve	erde and	Blanco) - Pero	cent of Centerl	ine mile	s					
LOS A, B, C, or D	65%	5%	5%	45%		50%			30%		
LOS E	10%	0%	55%	5%		10%		25%			
LOS F	25%	95%	40%	50%		40%			45%		
Daily Miles of Travel -											
Change in Vehicle Miles of Travel (VMT) compared to 2035 No Build- (000s)	N/A	0	40	-40	-140	-110	-200	-110	-90	-160	
Daily Hours of Travel -	Regional										
Change in Vehicle Hours of Travel (VHT) compared to 2035 No Build- (000s)	N/A	0	-80	-90	-100	-100	-130	-80	-80	-110	
April 29, 2010 Source: MPO Travel Demand Model, 2009, US 281 EIS Team, 2010											

Source: MPO Travel Demand Model, 2009, US 281 EIS Team, 2010



# 1.4 DRAFT EIS MODELING

2 This section describes the modeling performed for the Draft EIS alternatives screening.

# 3 1.4.1 Source Travel Model

- 4 The MPO updated the travel demand model prior to the time period of Draft EIS
- 5 screening. The improvements included changes to the volume delay functions utilized
- 6 in the model to reflect more realistic conditions on congested roads, but made little or no
- 7 changes to the network. The MPO transmitted new 2035 trip tables and networks on
- 8 June 3, 2010. The trip tables created by the MPO reflected the adopted 2035
- 9 socioeconomic data scenario (TOD + Infill) for the region. The overall number of
- 10 regional trips in 2035 remained approximately the same as for Level 2 and 3 screening.

# 11 1.4.2 2035 No-Build Network Model

- 12 The new network received from the MPO was reviewed to ensure that no new projects
- 13 were included in the vicinity of the study area. Then the No Build model forecast was
- 14 performed with the updated volume-delay functions and trip tables.

# 15 1.4.3 2035 Build Networks

19

20

21

22

23

24

25

26 27

28

29

30

31

32

33

34

- 16 The 2035 Draft EIS Build networks were coded for the Draft EIS Proposed Build
- 17 Alternatives using Level 3 alternatives as a base.
- 18 The Draft EIS Proposed Build Alternatives are described below:

# • Expressway Alternative (Figure 10)

This alternative would include frontage roads and an expressway with 3 through lanes plus auxiliary lanes in each direction for most of the US 281 project corridor. It includes 3 options for the mainline lanes:

- Non-toll This option was coded with free expressway lanes for the mainline.
- Toll This option was coded as toll expressway lanes, with toll costs of \$0.15 per mile for autos and \$0.40 per mile for trucks according to guidance from the MPO.
- Managed Lanes This option was coded with toll expressway lanes to simulate the availability of the lanes to toll vehicles. However, because HOV vehicles would also be able to use the facility, the toll cost was reduced to \$0.08 per mile for autos (thus attracting more vehicles to the lanes). Also, about 2,500 trips that use the US 281 project corridor were reduced from the trip table to account for the increased amount of carpooling.





# • Elevated Expressway Alternative (Figure 11)

May 2015

1

2

3

4 5

6

7

8

9

10

1112

13

1415

16


This alternative would be adjacent to the existing US 281 project corridor and would include an elevated expressway with 3 through lanes for most of the corridor. It includes 3 options for the mainline lanes:

- Non-toll This option was coded with free expressway lanes for the mainline.
- Toll This option was coded as toll expressway lanes, with toll costs of \$0.15 per mile for autos and \$0.40 per mile for trucks according to guidance from the MPO.
- Managed Lanes This option was coded with toll expressway lanes to simulate the availability of the lanes to toll vehicles. However, because HOV vehicles would also be able to use the facility, the toll cost was reduced to \$0.08 per mile for autos (thus attracting more vehicles to the lanes). Also, about 2,500 trips that use the US 281 project corridor were reduced from the trip table to account for the increased amount of carpooling.






# 1 Figure 10: Draft EIS Expressway Alternative Cross Sections



<u>2</u>

# 1 Figure 11: Draft EIS Elevated Expressway Alternative Cross Sections






# 1 1.4.4 Draft EIS Results

- 2 The summary results of the Draft EIS modeling are presented in Figure 12, Figure 13,
- 3 **Figure 14**, and **Table 4**.

4

Figure 12: Average Daily Traffic by Alternative




6 Source: US 281 EIS Team, 2010

5

1

# Figure 13: Average Peak Hour Speed by Alternative



Source: US 281 EIS Team, 2010


2

3



May 2015

### 1 Figure 14: Level of Service by Alternative



2 3

Source: US 281 EIS Team, 2010



# 1 Table 4: Detailed Draft EIS Travel Demand Measures of Effectiveness

May 2015

		Alternatives									
Level 3 Criteria	Existing	2035									
				Expressway			Elevated Expressway				
		No Build			Managad						
			Non-Toll	Toll	Managed	Non Toll	Toll	Managea			
Average Peak Hour Speed (mph) - Corridor											
South of Bulverde - US 281 Mainline	22	10	45	49	46	37	45	41			
South of Bulverde - US 281 Frontage Roads	-	-	30	28	30	33	25	31			
North of Sonterra - US 281 Mainline	15	9	35	40	37	34	41	39			
North of Sonterra - US 281 Frontage Roads	-	-	23	24	26	23	19	22			
Average Daily Traffic (000s)											
South of Bulverde - US 281 Mainline	40	80	125	115	120	115	100	110			
South of Bulverde - US 281 Frontage Roads	-	-	15	20	15	20	30	20			
South of Bulverde - Blanco + Bulverde	15	40	20	25	25	25	25	25			
North of Sonterra - US 281 Mainline	80	125	185	175	180	130	110	120			
North of Sonterra - US 281 Frontage Roads	-	-	20	20	25	50	60	50			
North of Sonterra - Blanco + Bulverde	55	110	65	65	60	80	85	70			
LOS along U.S. 281 Corn	ridor - Mai	nline - Perce	ent of Centerli	ne miles							
LOS D or Better	25%	0%	75%	75%		80%					
LOS E or F	75%	100%	25%	25%		20%					
LOS along U.S. 281 Cor	ridor - Fron	tage Roads	- Percent of Ce	enterline miles							
LOS D or Better	-	-	100%	100%		75%					
LOS E or F	-	-	0%	0% 25%							
LOS along Parallel Faci					es						
LOS D or Better	75%	0%	90%	90%		70%					
LOS E or F	25%	100%	10%	10%			30%				

<sup>2</sup> Source: MPO Travel Demand Model, 2009, US 281 EIS Team, 2011





1

2

This page intentionally left blank.